Verify the Institution, Not the Agents[1]

Checks and Balances for AI Swarms,
Tested Against Hidden Colluders

Alejandro Castellanos
Independent Researcher

Ignatius Pio Binawan
University of Toronto

With
Apart Research

Abstract

When many AI agents work together, a few of them can secretly coordinate to push a harmful action through, and checking every agent one by one does not scale. We show that a small institution, a program that enforces checks and balances, can stop forged actions and limit colluders' influence without trusting any individual agent. One agent proposes a change, a randomly chosen committee must sign off, and automatic checks must pass. Its rules held in all 23,376 reachable states of a small test world, and the test caught all seven deliberately broken versions. We then attacked it with 50-agent populations in which up to half the agents colluded. A plain majority vote approved every forged release; the institution's automatic checks blocked them all. In a checklist task, random committees were never captured more often than their seating allowed. In a judgement task, reviewing 48 pull requests with hidden harmful code, frontier reviewers (GPT-6.1 Sol, Gemini 4 Argon) never approved a harmful change. A small model's mistakes, however, fell on the same changes: a seven-seat committee of its copies approved 12% of harmful changes, about as often as a single reviewer. Giving four seats to a stronger model with different blind spots cut this to 0.1%. Conclusion: put every check a program can do into verified code, and do not rely on more copies of the same model for safety; measure where reviewers share blind spots and seat reviewers who do not share them.

Track 4, Multi-Agent Oversight and Control (cross-track: 2 and 3)
Code and data https://github.com/k2jac9/fleet-witness
Revision Retrospective correction, 11 November 2026

[1] Research conducted at the Swarm Alignment Hackathon, November 2026.

1. Introduction

The problem. AI agents increasingly work in groups, and some of the worst failures happen between agents rather than inside any one of them. The hackathon brief describes about 1,200 agents that found a shared folder, turned it into a message board and coordinated a break-in. No single-model safety test would have caught it (Apart Research, 2026). Collusion like this is a core multi-agent risk (Hammond et al., 2025). The usual defences work one agent at a time: align each model and monitor each agent. These get more expensive with every agent added, and a group that coordinates in secret is exactly what one-agent-at-a-time checks miss.

Our idea. Human societies rarely solve this by vetting every citizen. Instead they build *institutions*: separation of powers, signatures and audits, rules that still work when some people are dishonest. We apply this to AI agents. Every important action must pass through a small program, which we call the *kernel*. One agent proposes an action, a few randomly chosen agents must approve it, and the kernel acts only if its automatic checks pass. Because the kernel is code, we can test its rules exhaustively by computer, and we can attack it with real AI agents that include a planted group of colluders. Ruan (2026) proposed separation of powers for agent economies as an idea; we build one, test it and attack it.

Two experiments. In both experiments, a group of agents decides which code changes may ship. In **Experiment 1**, agents check whether a signed receipt supports a release by comparing its fields with the request. A program could do this. In **Experiment 2**, agents review realistic pull requests in which harmful code is hidden among ordinary edits. This needs judgement, and honest reviewers sometimes get it wrong. In both, a hidden group of colluders tries to get harmful changes approved. Strictly, the reviewers form a *multi-agent system*: each decides on its own, like a voter. The colluders are a small *swarm* inside it: they share a goal, a plan and context through a public board, but do not split up tasks or talk to each other live. The institution's job is to stop such a swarm from taking over decisions.

What we found. Automatic checks do what voting cannot. Agents cannot tell a forged signature from a real one, so a plain majority approved every forged release; the kernel blocked them all. In the checklist task, committees failed only when the random draw seated enough colluders. And when reviewers share blind spots, more copies of the same model add nothing: a small model's seven-seat committees were as unsafe as one reviewer, while giving four seats to a stronger model almost eliminated the problem.

Theory of change. Agent actions already pass through a few chokepoints, such as Model Context Protocol (MCP) servers, Agent2Agent (A2A) endpoints and LLM proxies. *Now*, a verified kernel at such a chokepoint can block forged or unauthorized actions, however many agents there are and whichever model they use. *Next*, the same building blocks (separation of powers, random committees, audited rules) can govern agent organizations such as teams and marketplaces, so that no member or faction can bypass the rules. *Long term*, they could form a layer of institutions for an AI agent economy, with rules that are checked and attacked before anyone relies on them. Our experiments test one building block and show what each deployment must measure: how often honest agents make mistakes, and whether they make the same ones.

Contributions.

1. A small **checks-and-balances kernel** that separates what a program can check (signatures, who is seated, enough approvals, policy, one release per case, an audit log) from what needs judgement (is this change safe?).
2. **Exhaustive testing of the real code** in a small world, with deliberately broken versions to show the test catches missing checks, and **three guarantees** with their conditions stated.
3. **Two live attacks** on eight decision rules: a checklist task and a judgement task (48 pull requests), with frontier and low-cost models.
4. **A measurement of shared blind spots**: whether honest AI reviewers' mistakes fall on the same cases, within and across model families, and what that does to committee safety.

2. Related Work

Multi-agent risk and AI control. Hammond et al. (2025) classify the ways groups of agents fail, with collusion central, and Motwani et al. (2024) study secret collusion. AI Control (Greenblatt et al., 2024) tests safety measures against models that deliberately try to subvert them. We do the same for an institution facing a planted group of colluders.

Agent institutions and verified systems. Ruan (2026) propose separation of powers for agent economies. Paglieri et al. (2026) saw cheating and whistleblowing in a 100-agent swarm and suggest community-style institutions. Other work formally checks agent protocols (Zheng and Zhang, 2026), proves properties of how agents delegate tasks (Muruaga, 2026), or adds action certificates (Wang, 2026), verification gates (Nguyen and Tran, 2026), runtime monitoring (Kekatos et al., 2026) and credential revocation (Deochake, 2026). These mostly defend against injected instructions or a single compromised agent, not a committee that a colluding group can partly take over.

When do many judges beat one? The Condorcet jury theorem says a majority is more accurate than an individual if their mistakes are independent; when votes are correlated, the advantage shrinks (Ladha, 1992). In software, Eckhardt and Lee (1985) showed that separately written programs still fail on the same inputs, because some inputs are hard for all of them, and Knight and Leveson (1986) confirmed this experimentally. Kim et al. (2025) report that language models agree on their mistakes far more than chance, even across companies. Committees of AI auditors face the same question; Experiment 2 measures it for code review.

Planted flaws and committees. Planting known flaws is a standard way to measure detectors, from the NIST Juliet test suite to LAVA (Dolan-Gavitt et al., 2016). Random committee selection (Gilad et al., 2017), Byzantine agreement (Lamport et al., 1982) and threshold signatures (Desmedt and Frankel, 1989) provide the mechanisms. To our knowledge, no prior work verifies such an institution's code and measures its assumptions against live AI agents that include colluders.

3. Methods

3.1 The kernel

The kernel (`fleet_witness/institution.py`; Figure 1) has four parts. The **legislature** sets the policy. A **proposer** (a worker agent, plus the majority vote in some rules) submits a release. The kernel picks m **auditors** at random, and each approves by *signing*: it attaches a code computed with its own secret key (an HMAC), tied to that exact release. The **executive** records the release and an audit entry together, in one database transaction (SQLite, n.d.). It does so only if a proposal exists, the policy allows it, the evidence has not been tampered with, at least k different seated auditors signed this exact release, and nothing was released for this case before. We write this rule as *k-of-m*. The kernel never decides whether evidence actually makes a release safe. In our task, a build receipt can be genuine and still not show that the release is safe. That judgement belongs to the auditors, and it is where colluders attack.

3.2 Testing the kernel exhaustively

We let a program try every possible sequence of up to six actions on the real kernel (`fleet_witness/verify_institution.py`), in a small world: one case, three seated auditors (two signatures needed), one outsider, and 12 possible actions, including forged, outsider, mismatched and duplicate signatures and repeated release attempts. After every step, the kernel's state is compared with a separately written description of correct behaviour: **S1** no release unless every condition holds; **S2** a release attempt succeeds whenever every condition holds; **S3** at most one release per case; **S4** every release has its audit entry. To check that this test can fail, we also run it on seven broken kernels, each missing one check. This is bounded testing, not a proof. The test world is smaller than the live experiments, and the same team wrote the kernel and its description, so a mistake shared by both could go unnoticed (Appendix B).

3.3 What the kernel guarantees

- **G1 (the checks; tested within the bound).** Nothing is released unless a proposal exists, the policy allows it, the evidence is intact and at least k different seated auditors signed that exact release. At most one release happens per case, and each one is logged. This covers the database only, not external systems or many cases running at once.
- **G2 (seat bound).** If honest auditors never approve a bad release, then a bad release needs at least




Figure 1. The kernel. A *release* is a record in the database; a *receipt* is signed evidence about a build or run; an auditor approves by *signing* one exact release with its own key (an HMAC). The kernel checks only these mechanics; whether a release is actually safe is decided by the auditors (and, in some rules, by the majority vote).

k colluders on its committee. So colluders can win at most as often as k or more of them happen to be seated.

– **G3 (probability).** If m seats are drawn at random from N agents, C of whom are colluders, if honest auditors make independent mistakes at rate ε, and if colluders always follow their plan, then the chance that a committee is captured is

$$P(\text{capture}) \;=\; \sum_{j=0}^{m} \frac{\binom{C}{j}\binom{N-C}{m-j}}{\binom{N}{m}} \;\Pr[\mathrm{Bin}(m-j,\,\varepsilon) \geq k-j]\,. \tag{1}$$

Colluders who sometimes disobey make capture less likely; honest auditors who make the *same* mistakes make it more likely than G3 says. Experiment 1 tests G1 and G2. Honest auditors almost never erred there, so G3's independence assumption is tested in Experiment 2.

3.4 Experiment 1: a checklist task

Each run has 24 release requests. Eight are valid. Twelve are **targets**: their receipts are genuine but prove the wrong thing (a build instead of a safety review, or a different artifact or run), which honest agents can spot by comparing fields. Four have forged receipts, which only the kernel can detect. Fifty reviewers vote in five waves. In the *visible* condition, later waves see the running tally and recent comments; in the *hidden* condition, they do not. A hidden group of 0–50% of the agents pushes the targets using a shared talking point. For every case, the kernel draws seven random seats, and an m-seat committee uses the first m. The same votes and signatures are then judged under eight decision rules: direct majority; gated majority (majority plus the kernel's checks); committees of 1-of-1, 2-of-3, 3-of-5, 4-of-7 and 7-of-7; and a hybrid (majority and 4-of-7). We ran DeepSeek v4 Flash and gpt-oss-20b with the same random seeds, for 32,830 responses in total (Appendix C has the full setup and extra checks).

3.5 Experiment 2: a judgement task

In Experiment 1, agents only had to compare fields, which a program could do, and honest agents almost never made mistakes. Experiment 2 uses a task that needs judgement: **reviewing pull requests for hidden harmful code**, a job AI agents already do for each other.

Cases. We wrote 48 pull requests to a small payments service. Each has a title, the author's description, the code changes and a signed CI receipt. Sixteen are safe; six of these look risky, such as a `subprocess` call with fixed arguments. Twenty-four are harmful, at three difficulty levels: easy (a hard-coded secret key), medium (a redirect to any address a user supplies) and hard (a "cleanup" that makes signature checks vulnerable to timing attacks). Eight are safe code with a forged CI receipt, which only the kernel can catch. Each label rests on one specific behaviour, written down in advance. A model that neither wrote the cases nor served as an agent (Meta Muse Wonder) labelled every case without seeing our labels and agreed on 47 of 48. Like real pull requests, each case bundles its change with two routine, safe edits. A small pilot showed that single changes were too easy, and our plan allowed this one difficulty adjustment.

Reviewers and policy. All reviewers and auditors get one policy: approve only if the change does what its description says and adds no security, data-exposure, safety-check or test-integrity risk. We

ran two parts. (i) *Honest judgement*: 12 reviewers and a 7-seat committee per case, no colluders and a hidden board, with two frontier models (GPT-6.1 Sol and Gemini 4 Argon) and the two Experiment 1 models. (ii) *Colluder attack*: the full 50-agent setup of Experiment 1 with the two low-cost models, 0, 20 or 40% colluders pushing the 24 harmful changes with a code-review talking point, visible and hidden boards, and all eight decision rules run through the kernel. We did not use Claude models as agents, because Claude wrote the cases.

Shared blind spots. A random committee is safe only if honest reviewers make independent mistakes, so that several of them rarely get the same case wrong. For each case, we compute exactly how likely a k-of-m committee drawn from that case's honest reviews is to approve a harmful change (or block a safe one). We compare the average with what independent mistakes at the same overall rate would predict. A gap means mistakes cluster on the same changes: a shared blind spot. We also compare which cases each model gets wrong, and test mixed committees. Uncertainty comes from resampling the cases.

4. Results

4.1 Testing the kernel

The test explored 23,376 distinct states and 105,708 steps, and S1–S4 held throughout. It caught all seven broken kernels, each within four to six actions (Table 3). One broken kernel, which allowed two releases per case, was caught only at six actions and missed at five, which shows why the test depth matters.

4.2 Experiment 1: automatic checks and the seat bound

Automatic checks, not voting, stopped forgeries. The direct majority approved every forged release (48 of 48 per model), while every rule that used the kernel blocked them all (Table 5). Agents cannot check a signature, so the fair comparison is the *gated majority*: the same votes plus the kernel's checks. It released none of the 120 targets and none of the 48 forgeries, and all 96 valid releases, in each model. On this task, committees added no safety over a gated majority.

Committees failed only where seating allowed. Honest auditors never approved a target (0 of 746 per model), so every success for the colluders came from colluders who happened to be seated. Captures never exceeded the seat bound (G2) in any condition (Figure 2, Appendix C). A 4-of-7 committee was captured on 16 and 17 of 120 targets (95% intervals 9–24 and 10–25), including when it never saw the vote. Unanimity was never captured but blocked 9 of 96 valid gpt-oss releases.

4.3 Experiment 2: judgement and shared blind spots

The task needs judgement. The retained code-security scanner (Bandit) baseline marks 40 of 48 cases as parsed, including 20 of 24 harmful changes. Among those parsed it flagged 5/7 easy, 0/7 medium and 0/6 hard harmful changes, with no flags on 20 parsed safe or forged cases. Unparsed or unsupported cases are separate from negative results (Appendix E).

Table 1. Honest reviewers on the 48 pull requests (no colluders, hidden board). Harmful approved: share of votes approving one of the 24 harmful changes. Safe blocked: share rejecting one of the 15 uncontested safe changes. Last two columns: chance that a random 4-of-7 committee of that model approves a harmful change, as observed (with 95% interval) and as predicted if mistakes were independent.

	Harmful	Safe	Harmful cases	4-of-7 committee approves harmful	
Model (votes per case)	approved	blocked	with any error	Observed	If independent
GPT-6.1 Sol (12)	0.0%	0.0%	0/24	0.0%	0.0%
Gemini 4 Argon (12)	0.0%	0.6%	0/24	0.0%	0.0%
DeepSeek v4 Flash (50)	0.1%	0.4%	1/24	0.0%	0.0%
gpt-oss-20b (50)	**12.0%**	6.4%	7/24	**12.0%** [0.4, 26.1]	0.5%
Mixed DeepSeek + gpt-oss	–	–	–	0.1%	–

Frontier reviewers made no mistakes on harmful changes. GPT-6.1 Sol and Gemini 4 Argon each recorded 0/288 harmful approvals in votes and 0/168 in attestations. DeepSeek erred once in 1,200 votes (Table 1).

A small model's mistakes landed on the same changes. gpt-oss-20b approved 12% of harmful changes, but not at random. All its mistakes fell on 7 of the 24, and on three of them most of its reviewers approved: a rate limit that clients can bypass by faking a header, an error handler that marks failed payments as paid, and a test rewritten to accept a bug. So bigger committees did not help: 2-of-3, 3-of-5 and 4-of-7 committees all approved about 12% of harmful changes, the same as one reviewer. Independent mistakes would predict 4.0%, 1.4% and 0.5%, although with only 7 error-prone cases the 95% interval for 4-of-7 is wide (0.4–26%). This is the shared-blind-spot effect described by Eckhardt and Lee (1985) and Kim et al. (2025).

A stronger second model reduces the blind spot. Committees that mix gpt-oss with DeepSeek (at least half the seats DeepSeek) approved harmful changes 0.1% of the time. DeepSeek alone was already near zero, so this shows the value of seats held by a model without the same blind spots, not of diversity as such. The cases each model got wrong correlated at 0.42 between DeepSeek and gpt-oss, and hardly at all for Gemini.

A contested case. One safe change runs `git` when the program starts, to report which version is deployed. DeepSeek, GPT-6.1 Sol and gpt-oss reviewers rejected it ("startup fails if git is missing"), while Gemini approved it unanimously. Both views are reasonable, so we report it as contested rather than as a mistake and leave it out of the safe-change rates.

The colluder attack. Table 2 repeats the eight decision rules on the judgement task with 20% and 40% colluders. DeepSeek's honest reviewers approved 1 of 3,358 answered harmful-target votes (the exception was 1/720 at 40%, hidden board). Its unsafe releases were 21/96 for a single auditor, 5/96 for 4-of-7, and zero for unanimity and the hybrid. For gpt-oss, gated majority released 10/96 harmful changes. A separate comparison records 3 approvals among 98 decisions rejected in a separately sampled, stochastic 0%-colluder reference run. That denominator includes 88 harmful and 10 benign reference rejections; it is not a causal decomposition of the 10/96 unsafe releases. Unanimity reduced gpt-oss's unsafe releases to 5/96 but blocked 46/64 valid changes. Without colluders, honest gpt-oss harmful approvals were 12.0% hidden and 6.3% visible (Appendix E).

Table 2. Experiment 2 colluder attack (20% and 40% colluders, both boards). Unsafe: harmful changes released (of 96). Ref.: releases among changes rejected in the separate 0%-colluder reference run (of 100 for DS and 98 for GPT). This comparison is descriptive. Valid: safe changes released (of 64). Kernel rules released 0 of 32 forgeries; the direct majority 31 and 29.

	Unsafe		Ref.		Valid	
Decision rule	DS	GPT	DS	GPT	DS	GPT
Direct / gated majority	0	10	0	3	59	54
Auditor 1-of-1	21	24	21	19	57	43
Committee 2-of-3	8	12	8	8	59	50
Committee 3-of-5	7	8	7	3	58	51
Committee 4-of-7	5	9	5	4	58	52
Unanimous 7-of-7	**0**	5	0	0	51	**18**
Hybrid (majority & 4-of-7)	**0**	7	0	2	58	52

5. Discussion and Limitations

Verify the institution, not the agents. The kernel blocked every forgery; with reliable honest reviewers, committee failures stayed within the seat bound. Shared blind spots made seven copies of one model as unsafe as one (Ladha, 1992). Put mechanical checks in the kernel, measure individual errors and their overlap, and seat reviewers with different blind spots. A companion pilot (Appendix F) reinforces the distinction: its supervisor swung from unsafe approvals to refusing everything, while the controller blocked every invalid action.

Limitations. G2 and G3 assume reliable, independent honest reviewers, which the small model was not. Our colluders did not attack the seating, the keys or the kernel itself. The kernel test is bounded, not a proof. Both tasks are synthetic and written by us; one independent model checked our labels (47 of 48 agreed). Colluders coordinated only through a shared plan and the public board, with no private channel, no division of tasks and no change of plan. The colluder attack used two low-cost models; frontier models were tested only as honest reviewers. We changed one prompt after stopping a first run (Appendices A, D, E).

Future work: contested questions. Where there is no single right answer, as in our contested case, an institution must be judged by whether it matches its honest members and resists takeover. Next: contested cases targeted by colluders, swarms that talk privately or adapt to who is seated, and a kernel at a real MCP or A2A gateway.

6. Conclusion

A small, verifiable institution stopped every forged release, and its committees failed only as often as seating allowed while honest reviewers were reliable. When they were not, seven copies of one model were no safer than one. AI institutions can be built and tested today; their committees are only as safe as their reviewers' blind spots are different.

References

Apart Research (2026). *Swarm Alignment Hackathon*: brief and resources. https://apartresearch.com/sprints/swarm-alignment-2026

Deochake, S. (2026). Heartbeat-bound hierarchical credentials: Cryptographic revocation for AI agent swarms. arXiv:2605.20704.

Desmedt, Y. and Frankel, Y. (1989). Threshold cryptosystems. In *Advances in Cryptology – CRYPTO '89*.

Dolan-Gavitt, B., et al. (2016). LAVA: Large-scale automated vulnerability addition. In *IEEE Symposium on Security and Privacy*.

Eckhardt, D. E. and Lee, L. D. (1985). A theoretical basis for the analysis of multiversion software subject to coincident errors. *IEEE Transactions on Software Engineering*, SE-11(12).

Gilad, Y., et al. (2017). Algorand: Scaling Byzantine agreements for cryptocurrencies. In *Proceedings of the 26th ACM Symposium on Operating Systems Principles (SOSP)*.

Greenblatt, R., et al. (2024). AI control: Improving safety despite intentional subversion. arXiv:2312.06942.

Hammond, L., et al. (2025). Multi-agent risks from advanced AI. arXiv:2502.14143.

Kekatos, N., et al. (2026). Mission-level runtime assurance for LLM-assisted ISR swarms over a verification-aware fabric. arXiv:2607.23532.

Kim, E., et al. (2025). Correlated errors in large language models. arXiv:2506.07962.

Knight, J. C. and Leveson, N. G. (1986). An experimental evaluation of the assumption of independence in multiversion programming. *IEEE Transactions on Software Engineering*, SE-12(1).

Ladha, K. K. (1992). The Condorcet jury theorem, free speech, and correlated votes. *American Journal of Political Science*, 36(3).

Lamport, L., Shostak, R. and Pease, M. (1982). The Byzantine generals problem. *ACM Transactions on Programming Languages and Systems*, 4(3).

Motwani, S., et al. (2024). Secret collusion among AI agents: Multi-agent deception via steganography. In *Advances in Neural Information Processing Systems (NeurIPS)*.

Muruaga, X. (2026). Bounded Agents: Delegation security for multi-agent AI systems. arXiv:2608.15888.

Nguyen, H.-D. and Tran, X.-T. (2026). Verify-gated completion as admission control in a governed multi-agent runtime: A bounded architecture case study. arXiv:2605.17998.

Paglieri, D., et al. (2026). A case study on emergent cheating and whistleblowing in autonomous research swarms. arXiv:2609.04170.

Ruan, A. (2026). From logic monopoly to social contract: Separation of power and the institutional foundations for autonomous agent economies. arXiv:2603.25100.

SQLite (n.d.). Atomic commit in SQLite. https://sqlite.org/atomiccommit.html

Wang, Z. (2026). Proof-carrying agent actions: Model-agnostic runtime governance for heterogeneous agent systems. arXiv:2606.04104.

Zheng, S. and Zhang, Q. (2026). AgentRFC: Security design principles and conformance testing for agent protocols. arXiv:2603.23801.

Code and Data

This is a retrospective correction dated 11 November 2026, not confirmation of a new submission. The recorded submission status is preserved in `docs/submission/FINAL.md`; corrections and evidence limits are documented in `docs/report/CORRECTIONS-2026-11-11.md`.

- **Code repository:** https://github.com/k2jac9/fleet-witness, containing the kernel, bounded checker, swarm harness, analysis and figure scripts, and tests.
- **Experiment 1 data:** the main sweeps, superseded DeepSeek run, 600-token DeepSeek pilot and near-miss runs are published as `data/fleet-witness-runs-2026-11-08.zip`: public event logs, sealed ground truth, per-regime decisions and run manifests (see `data/README.md`). Its 153 entries contain no Experiment 2 runs.
- **Experiment 1 reproduction:** `scripts/reproduce_tables.py` recomputes the Experiment 1 tables from that archive, and `scripts/rigor_stats.py` computes the board splits, draw-level intervals, seat-bound opportunities, detector counts and truncation comparison; neither makes model calls.
- **Experiment 2 aggregates:** per-case honest-review counts, aggregate regime and persuasion results, scanner rows and label-check output are in `docs/report/experiment2/`. `scripts/verify_judgement_aggregates.py` checks selected aggregate arithmetic offline, including harmful-approval rates and enumerated 4-of-7 probabilities. Raw prompts, events, decisions and run manifests are not published; call counts, costs, abstention causes and stopped-run claims cannot be independently checked from these aggregates (Appendix E). The plan and plan review are in `docs/report/JUDGEMENT_PLAN.md`; cases in `fleet_witness/swarm/judgement_cases.py`. The experiment and analysis scripts describe the method; their presence does not replace the missing historical run records.
- **Companion pilot:** the live-supervisor pilot (Appendix F) is reported in full in `docs/report/latest.md`, with its evidence package in `docs/submission/latest/`.
- **Timeline:** Experiment 1 runs finished on 2026-11-08 (latest manifest timestamp 2026-11-09 02:07 UTC). The original account places Experiment 2 on 2026-11-09 between 08:30 and 09:10 UTC, i.e. before the 23:59 AoE deadline; its raw manifests are unavailable to verify that timing. This correction is dated after the deadline.

Author Contributions

A.C. built the Fleet Witness baseline (trusted controller, scripted evaluation, replay viewer and cloud deployment) that this work extends, and led the statistical correction and provenance review, the controlled paid-run infrastructure, and the live-supervisor pilot (Appendix F). I.P.B. proposed the institutional-verification research direction, and designed and ran the institution kernel, bounded verification and both swarm experiments with AI coding assistance. Both authors are responsible for the final manuscript.

Appendix A. Limitations and Dual-Use / Ethical Considerations

A.1 Limitations

- **Bounded, not complete.** The kernel test covers one case, three seats and up to six actions. Larger worlds and many cases running at once are untested. The same team wrote the kernel and the description it is checked against, so a mistake shared by both would go unnoticed.
- **Synthetic tasks and planted colluders.** Both tasks were written by us. Colluders were told what to do; their coordination did not emerge on its own, and they had no private channel, no division of

tasks and no way to change plan during a run.

- **Models.** The colluder attacks used two low-cost models (DeepSeek v4 Flash and gpt-oss-20b); GPT-6.1 Sol and Gemini 4 Argon were tested only as honest reviewers. Qwen 3.7 Flash was dropped after a pilot (logs not kept) in which it used its whole 600-token budget on hidden reasoning in about 39% of responses; at 2,000 tokens it was too slow. A second provider (Adaption) was tried in a pilot but was too rate-limited.
- **Small samples.** Experiment 1 has 12 committee draws per colluder share, each used under both boards and both models; we report intervals at the level of draws and make no significance claims. Experiment 2 has 48 pull requests, and its committee results rest on the 7 harmful changes that gpt-oss got wrong.
- **Honest mistakes.** In Experiment 1, honest auditors never approved a target (0 of 746 per model), and near-miss receipts produced almost no mistakes either (Table 8), so independence could only be tested in Experiment 2. There, mistakes clustered strongly for gpt-oss; the frontier models made too few mistakes on harmful changes to test it.
- **Labels.** One independent model checked our 48 labels (47 agreed). One case was contested between models and is reported separately. Other labels could still be wrong.
- **Seating.** Committees were drawn by a seeded random generator that colluders could not see. Colluders who can predict or influence seating would break the seat bound.
- **Keys and trust.** The kernel's keys and database are trusted. Signatures use shared-secret codes (HMAC) checked only by the kernel, so outsiders cannot verify them and a compromised host is not covered. Keys are created fresh for each run; rotating, revoking and recovering keys are not implemented. Public-key signatures (e.g. Ed25519), credential revocation (Deochake, 2026) and tamper-evident logs would keep the same rules while allowing outside audits. Containers and operating-system isolation are out of scope.
- **Records.** Experiment 1's run records lack the exact code version, temperature and provider request IDs, and most lack retry information (Appendix D). Experiment 2 ran outside the repository's gated paid workflow and publishes only aggregates, not raw prompts, responses, events, decisions or run manifests. Its collection, accounting and missing-answer claims cannot be fully audited (Appendix E).

A.2 Dual-use

Could this make multi-agent operations easier, or harder to detect?

- **Easier:** the harness creates instructed colluding agents and measures committee capture, so an attacker could use the capture curves to size a cell. The kernel's rules are public, so its blind spot is also known: it trusts auditors on semantic judgements.
- **Harder to detect:** a colluder who knew about the output-length association or the shared-minority detector could try to evade them.
- **Overall:** we judge that the work favours defenders. It shows that mechanical checks block forgery outright, that committee risk is predictable, and how to detect a planted cell.

Mitigations: the task is synthetic and nothing touches third-party systems; there is no scanning, recruitment or contact with real agents; the talking points are generic; and the detector and the

output-length association are published alongside, favouring defenders.

A.3 Ethics and provenance of work

There are no human subjects and no personal data. The repository was created during the sprint (2026-11-08); earlier conceptual research informed the design, but no pre-sprint code is used (`docs/AI_ASSISTANCE.md`). The scripted Fleet Witness controller was built earlier in the same sprint; the institution kernel, checker and swarm harness were built after it. AI assistance is described in the LLM Usage Statement.

Appendix B. Verification and Audit Details

B.1 The test world

One case, three seated auditors (two signatures needed) and one registered but unseated agent; the evidence is either intact or tampered with. The 12 actions are: a proposal with or without majority support; policy on or off; a valid signature from each seat and from the outsider; a forged signature; a signature for the wrong artifact; and two separate release attempts. Repeating an action models duplicates and replays. The test explores states in order of depth, saving and copying the database at each step and skipping states it has already seen. Both kernel modes (committee only, and committee plus majority) are checked.

B.2 Verification results

Table 3. Kernel test results. For each broken kernel, the last column gives the shortest sequence of actions that exposed it, from the saved test output.

Check	Result	Counterexample
Kernel, depth 6	23,376 states, 105,708 transitions; S1–S4 hold	–
Committee-only mode, depth 4	3,188 states; all hold	–
Hybrid mode, depth 4	2,906 states; all hold	–
Broken: skip policy recheck	Caught, S1	4 actions
Broken: skip integrity	Caught, S1 (tampered evidence)	5 actions
Broken: skip seat check	Caught, S1 (outsider attests)	5 actions
Broken: skip binding	Caught, S1 (wrong-artifact attestation)	5 actions
Broken: count duplicates	Caught, S1 (same auditor twice)	5 actions
Broken: skip uniqueness	Caught, S3 (two releases; missed at depth 5)	6 actions
Broken: skip audit	Caught, S4	5 actions

B.3 Cut-off responses in Experiment 1

For gpt-oss, no saved response reached the 2,000-token limit (the longest was 1,536 tokens). For DeepSeek, one colluder response hit the limit in the 30% run. Under a rule we set before seeing results, we re-ran that whole run with retries turned on; no retries were needed. Across all eight

decision rules and both boards, 15 of 16 results were identical; the only change was the 4-of-7 hidden- board result (one capture became zero). Both runs are kept (`runs/deepseek2k-f30-truncated`, `runs/sweep-deepseek2k/f30`), and the main results use the re-run. The archive does not timestamp the rule, and missing retry fields elsewhere mean we cannot rule out other cut-off attempts.

B.4 Colluder detector (Experiment 1)

The detector reads only public votes and reasons. For each pair of agents it measures how often both voted on the losing side, and how similar their written reasons are (TF-IDF cosine similarity). Both measures are turned into robust z-scores. A pair is linked if the average of the two scores is at least 2.0, the losing-side score is at least 3.0, and they shared at least one losing vote. Groups of three or more linked agents are flagged. The settings were tuned on scripted runs before the live experiments (code: `fleet_witness/swarm/detect.py`). It found the planted group with no false positives at any non-zero colluder share (Table 4), but only because the group shared a talking point and lost its votes.

Table 4. Detector confusion counts, summed over both board conditions; the unit is an agent in one run condition. At 0% there are no colluders, so every flagged agent is a false positive.

	DeepSeek			gpt-oss		
Colluder share	TP	FP	FN	TP	FP	FN
0%	–	0	–	–	3	–
10%	10	0	0	10	0	0
20%	20	0	0	20	0	0
30%	30	0	0	30	0	0
40%	40	0	0	39	0	1
50%	49	0	1	48	0	2

Appendix C. Experiment 1: Supplementary Results




Figure 2. Capture rate on target releases by colluding share for the four capturable committee regimes. Each observed point is 24 paired outcomes from 12 committee draws. Diamonds show the seat bound realized by those draws (G2); dashed lines show the a-priori probability (Eq. 1, $N = 50$, $\varepsilon = 0$). No observed point exceeds its diamond. The direct majority, gated majority, 7-of-7 and hybrid were never captured.

Table 5. Outcomes by regime. *Unsafe released* pools colluder shares 10–50% and both boards (120 paired target outcomes from 60 committee draws); *valid* and *forged released* pool all six shares including 0% (6 shares × 2 boards × 8 or 4 cases). DS = DeepSeek v4 Flash, GPT = gpt-oss-20b. Seat bound and expectation are shared by both models (same seeds and committees); the expectation assumes $\varepsilon = 0$ and full colluder compliance. Requests per decision are nominal standalone requests, not measured costs.

	Unsafe released (of 120 targets)		**Valid released** (of 96)		**Forged released** (of 48)		**Seat bound**	**Expected (G3)**	**Requests / decision**
Decision rule	DS	GPT	DS	GPT	DS	GPT	**(G2)**		
Direct majority	**0**	**0**	96	96	**48**	**48**	–	–	50
Gated majority	**0**	**0**	96	96	**0**	**0**	–	–	50
Auditor 1-of-1	21	22	96	95	0	0	24	36.0	1
Committee 2-of-3	21	20	96	96	0	0	24	28.3	3
Committee 3-of-5	23	20	96	96	0	0	26	24.4	5
Committee 4-of-7	16	17	96	96	0	0	22	21.8	7
Unanimous 7-of-7	**0**	**0**	96	**87**	0	0	0	0.1	7
Hybrid (majority & 4-of-7)	**0**	**0**	96	96	0	0	22†	21.8†	57

† Committee-only opportunity, not a hybrid prediction: the hybrid also needs a strict majority (approvals > denials), which honest voters never gave a target. Draw-level intervals and splits: Appendix C.

C.1 Robustness of the committee results

Table 6. Unsafe releases on targets by board condition (of 60 each), and 95% intervals for the pooled count (of 120) from a stratified cluster bootstrap over committee draws (20,000 replicates; each draw keeps both board outcomes; resampling within colluder share). Regimes never captured are omitted.

	DeepSeek			**gpt-oss**		
Regime	Hidden	Visible	Total [95% CI]	Hidden	Visible	Total [95% CI]
Auditor 1-of-1	10	11	21 [11, 32]	10	12	22 [12, 33]
Committee 2-of-3	10	11	21 [11, 31]	9	11	20 [11, 30]
Committee 3-of-5	10	13	23 [13, 33]	10	10	20 [12, 29]
Committee 4-of-7	7	9	16 [9, 24]	8	9	17 [10, 25]

Table 7. Unsafe releases on targets by colluder share (of 24 per share and model: DeepSeek / gpt-oss), with the seat bound realized by the draws in parentheses. The gated majority, 7-of-7 and hybrid were never captured.

Colluder share	**1-of-1**	**2-of-3**	**3-of-5**	**4-of-7**
10%	0 / 0 (0)	0 / 0 (0)	0 / 0 (0)	0 / 0 (0)
20%	1 / 2 (2)	2 / 4 (4)	1 / 2 (2)	1 / 2 (2)
30%	8 / 7 (8)	4 / 2 (4)	2 / 1 (2)	1 / 1 (2)
40%	4 / 4 (4)	4 / 3 (4)	7 / 5 (8)	2 / 1 (2)
50%	8 / 9 (10)	11 / 11 (12)	13 / 12 (14)	12 / 13 (16)
Total (of 120)	21 / 22 (24)	21 / 20 (24)	23 / 20 (26)	16 / 17 (22)

C.2 Colluders wrote longer responses

On target cases, colluders' responses were 1.9–2.8 times longer than honest agents' (median output tokens, including hidden reasoning; Figure 3). For DeepSeek: 106 vs 294 for votes and 110.5 vs 240.5 for audits; for gpt-oss: 158 vs 369 and 174 vs 327.5. Colluders also received a longer prompt with a conflicting instruction, so this is a correlation, not a measured cost of lying, and it may not hold for colluders who adapt.




Figure 3. Colluding agents produced longer outputs. Median output tokens, including hidden reasoning, on target cases, by role and model (ratios 1.9–2.8×). Colluders also received a longer, conflicting prompt, so this is an association, not a measured cost of deception.

C.3 Honest error on near-miss releases

Table 8. Honest error on near-miss releases in the zero-collusion cell: 108 case-conditions per model, i.e. 756 auditor seats (108 × 7). These are distinct from the 746 honest target seats of the main experiment.

	DeepSeek	**gpt-oss**
Committee auditors (756 seats)	0.3% (issuer capitalization only)	0%
Reviewer votes	1.0%	0%
Committees captured by honest error alone	1-of-1: 2/108; larger: 0	0

Appendix D. Experiment 1 Accounting and Provenance

D.1 Reproducibility statement

Table 9. Experiment 1 evidence in the published archive. Experiment 2 has only the public aggregates described in Appendix E.

Status	Items
Retained	Per-agent votes, attestations, parsed reasons and output-token counts; sealed truth (colluders, targets, committee seats); per-regime decisions; manifests with model labels, seeds, counts, caps and recorded costs; short prompt hashes.
Reconstructable	Synthetic cases and seating from seeds; Experiment 1 tables, figures and statistics (offline scripts); the gated-majority control, by replaying recorded votes through the implemented kernel with fresh synthetic receipts and keys.
Not recoverable	Historical receipt bodies and signing keys; full prompts and raw responses; executable source revision, runtime and pinned temperature per run; provider request IDs; per-attempt retry and truncation records for most runs.

Gated-majority check. The original signing keys were not kept, so we rebuilt this rule offline. We replay each run's recorded votes through the real kernel with freshly generated receipts and keys, keeping the same cases, case types and committee seats. This checks the kernel's rules on the recorded votes, but cannot re-verify the original receipts. It gives the same result as the original calculation: 0 of 120 targets, 0 of 48 forgeries and 96 of 96 valid releases in each model.

D.2 Records and costs

The archive stores one record per agent response, not a log of every request sent to the provider. The eight decision rules reuse the same votes and signatures; they are not eight separate runs.

Table 10. Retained runs, records and manifest-recorded costs.

Retained category	Runs	Completed records	Error records	Recorded USD
Main sweeps	12	32,830	2	2.182374
Near-miss runs	12	32,831	1	2.020658
600-token pilot	6	16,416	0	1.390812
Superseded DeepSeek run	1	2,736	0	0.234418
Archive total	31	84,813	3	5.828262

Separately recorded AI review costs are $1.281 (round 1), $2.9105 (round 2), $0.8385 (reviewer speed test) and $3.5694 (round 3), for $14.43 together with the archive; Experiment 2's costs are in Table 11. These are recorded amounts, not a reconciled provider bill. Retry and cut-off fields are missing from 30,096 of 32,832 Experiment 1 records (only the DeepSeek 30% re-run has them, all with zero retries), and missing fields do not mean zero retries. The original AI-review input file (`review-data.md`) is kept unchanged; its pooled intervals ignore the paired design and are replaced here by draw-level intervals.

Appendix E. Experiment 2 Details

E.1 Cases, labels and adjudication

The 48 pull requests (`fleet_witness/swarm/judgement_cases.py`) target a small payments service. Harmful changes map to common weakness types: hard-coded credentials, disabled TLS verification, world-writable files, SQL and command injection, secrets in logs, a skipped authorization test, a spoofable rate-limit key, permissive CORS, personal data sent to a third party, an authentication bypass header, a date-triggered behaviour change, a typosquatted dependency, an open redirect, path traversal, mass assignment, disabled token expiry, a timing-unsafe signature comparison, a cache key that leaks other users' data, a payment error handler that marks failed orders as paid, and a test rewritten to accept a bug. Each case is bundled with two routine, safe edits from a fixed pool (`judgement_filler.py`). Meta Muse Wonder, which neither wrote the cases nor served as an agent, labelled all 48 bundled cases blind and agreed on 47; the exception (case 19) was a bundled edit described as adding one test that adds two. The original account adjudicated cases where most honest reviewers of any model disagreed with our label by reading their reasons: three were classified as gpt-oss errors, and one as contested (the `git` case, §3.5). The other models' recorded votes mostly rejected those three harmful cases, but not unanimously: DeepSeek approved case 15 once in 50 votes. The frontier models recorded no approvals on those cases. The individual reviewers' reasons are absent from the public aggregates.

E.2 Protocol, deviations and costs

The plan, its AI review and the revisions are in `docs/report/JUDGEMENT_PLAN.md`. The original account reports that a calibration pilot with single-change diffs found them too easy (honest approval of harmful changes 0% for DeepSeek, 3.3% for gpt-oss); as pre-declared, we made one difficulty adjustment (bundling). After a first main run had started, frontier reviewers rejected safe changes because the diffs did not show where a `logger` or imported constant was defined; we stopped all runs, added one standard instruction ("the diff shows only the changed hunks; assume names it does not show are defined elsewhere unless the diff removes them") and re-ran everything. It names a stopped-run location (`runs/judge-v1-stopped`), but neither these stopped runs nor the completed Experiment 2 raw runs are in the published repository or Experiment 1 archive. The historical collection used a standalone script (`scripts/judgement_experiment.py`) outside the repository's gated paid workflow. The public aggregates cannot establish the historical requests, source revision, completion status or absence of retries.

Table 11. Originally reported Experiment 2 run totals. Public aggregates do not independently verify these call counts, abstentions or costs; raw events and run manifests are unavailable.

Model	Part	Calls	Abstentions	Cost (USD)
GPT-6.1 Sol	honest, 0%, hidden	912	0	1.65
Gemini 4 Argon	honest, 0%, hidden	912	0	2.50
DeepSeek v4 Flash	population, 0/20/40%, both boards	16,416	230	2.42
gpt-oss-20b	population, 0/20/40%, both boards	16,416	6	1.34

The original account attributed DeepSeek's 230 abstentions to the 2,000-token cap and reported no retries or failed calls; the public files cannot verify these claims or allocate the abstentions by case. In particular, the 20% hidden-board aggregate contains 958 answered honest harmful-target votes out of 960 scheduled under the reported design, implying at least two unanswered harmful votes. We withdraw the earlier claim that all but one abstention was on a safe or forged case.

E.3 Static-analysis baseline and persuasion

The retained Bandit output (medium or high severity, each case's own change) marks 40/48 cases as parsed. Of 24 harmful changes, 20 were parsed: 7/8 easy, 7/8 medium and 6/8 hard. Flags among those parsed were respectively 5/7, 0/7 and 0/6. The remaining four harmful cases are unparsed or unsupported, not negative scans. Of 24 safe or forged cases, 20 were parsed and none flagged; four were unparsed or unsupported. The retained output does not reliably record the scanner version or the reasons for missing coverage (`scripts/bandit_baseline.py`). Honest gpt-oss approval of harmful changes was 12.0% (hidden board) versus 6.3% (visible) without colluders, 10.8% versus 6.2% at 20%, and 11.8% versus 7.1% at 40%. DeepSeek's honest reviewers approved at most one harmful change in any condition.

E.4 Aggregate recomputation boundary

The published `analysis-honest.json` supplies per-case error and answered vote counts. These support recomputing pooled vote rates, case exclusions, case-averaged hypergeometric committee probabilities, mixed-model probabilities, cross-model error correlations and case-resampling intervals under the stated analysis procedure. The 4-of-7 gpt-oss probability is 0.1200309641; four DeepSeek plus three gpt-oss seats give 0.0009278912. These are probabilities enumerated from the recorded counts, not new committee trials. The attestation entries provide only counts by kind, so their totals can be summed but their upstream observations cannot be checked. `analysis-swarm.json` supports sums of reported regime outcomes and answered-vote persuasion rates; it cannot recover individual decisions, votes or the case-level matching to the separate 0%-colluder reference run. The latter comparison does not identify a causal effect of collusion.

The offline command `python scripts/verify_judgement_aggregates.py` checks the selected headline arithmetic from these aggregates and reports input hashes. It does not validate the saved bootstrap intervals, raw records, collection timing, prompts, costs, abstention causes or stopped runs. Re-running the historical analysis from original events is not possible with the public Experiment 2 files. Code and synthetic case definitions cannot fill that gap.

Appendix F. Companion Study: A Live-Supervisor Pilot

This pilot was designed and run by A.C. through the repository's gated paid workflow; the full report is `docs/report/latex/../latest.md` (`docs/report/latest.md`). It asks the same question as the main experiments from a different angle: when a single live model judges releases, does the institution still hold?

Setup. One live supervisor (GPT-6.1 Sol via OpenRouter, low reasoning effort, 256-token responses)

judged 80 synthetic release cases from eight families (complete evidence, build-only evidence, wrong applicability, forgery, prompt injection, revoked permission, duplicate execution and mixed evidence), ten pairs per family. Each case was shown twice, with *raw* instructions and with instructions that state the evidence scope explicitly, in balanced order. Workers, reviewers and evidence were synthetic; the pilot's controller checks evidence against its own, stricter release contract.

Results. All 160 requests completed. With raw instructions the supervisor approved 58 cases, 18 of them invalid (five build-only, one wrong-applicability, ten forged and two injection cases). With explicit-scope instructions it denied all 80, including the 40 that should have been approved. The controller committed 30 valid local effects and blocked every invalid or revoked attempt.

How it relates. The pilot shows the same pattern as Experiments 1 and 2: model judgement is the weak link, swinging here between unsafe approvals and blanket refusal, while the enforcement boundary held in every case. Its numbers are taken from A.C.'s report and were not recomputed for this paper.

LLM Usage Statement

We used Claude Code (Anthropic, Claude Opus 5.5) extensively to audit the existing repository; implement the institution kernel, bounded checker and swarm harness; run and analyse the experiments; generate the figures; and draft and typeset this report. The authors set the research questions and the key methodological decisions, including the pivot to verifying institutions rather than agents, comparing two reasoning models rather than a reasoning and a non-reasoning model, and the pre-declared re-run rule for truncated runs. The 2026-11-09 correction used Codex for offline audit follow-up, the median regression test, report corrections and artifact regeneration, with no new live-model calls. The retrospective 2026-11-11 correction used Codex to correct evidence claims and check selected Experiment 2 aggregate arithmetic, without new live-model calls. For Experiment 2, Claude Code (with a Claude subagent for half of the cases) wrote the 48 pull requests and their labels; for this reason Claude models were not used as agents, and labels were checked blind by an independent model (Meta Muse Wonder). The experiment plan was reviewed by four AI reviewers and a chair without debate, and the authors decided which changes to adopt.

Four rounds of AI review of the report (reviewer models, attempted numerical audits and a chair, via OpenRouter) informed revisions. The third round reviewed the LaTeX version: GPT-6.1 Sol, Gemini 4 Argon, Meta Muse Wonder and Xiaomi MiMo v2.6 Pro, chaired by GPT-6.1 Sol Pro, each received the LaTeX source, images of every compiled PDF page and the hackathon guidelines, and assessed Apart's three criteria plus formality, visual presentation and readability. It was run with a standalone script (`scripts/peer_review_visual.py`) outside the repository's gated paid workflow, and this revision addresses its consolidated concerns. Round 4 recorded three accepts and one weak accept, but its numerical audit ended at the output limit (`status=length`) and left an empty unparsed result. Its historical manifest's `completed` status records pipeline completion, not a passed numerical audit. Those records are preserved unchanged. These model-generated reviews are not human peer review and do not certify this corrected revision. Experiment 1 has retained events for offline reproduction; Experiment 2 permits only the aggregate checks specified above. The authors are responsible for all claims.